

PUNJAB HERITAGE AND TOURISM PROMOTION BOARD

PLOT NO. 3, SECTOR-38A, CHANDIGARH



No. 2876

Date: 10/9/21

Quotation Notice

Sealed quotations for the Repair Work of PTDC Record Room, Plot No.3, Sector -38A, Chandigarh from the approved contractors are here by invited:

Sr. No.	Name of Work	Estimated amount	Time limit
1.	Repair work of PTDC Record Room, Plot No.3, Sector -38A, Chandigarh	28,494/-	15 days

Submission and opening of quotations:-

The quotations will be received upto 3.00pm on 20.09.2021 and will be opened on the same date at 3.30pm in the office of Punjab Heritage & Tourism Promotion Board, Plot No.3, Sector-38A, Chandigarh in the presence of the quotationers or their duly authorised representative who may like to be present. In case the date of quotation is declared a gazetted holiday, the quotations will be opened on the next working date at the same time.

General Conditions:

1. TDS, as applicable will be deducted from all payments, made in respect of the work done.
2. Participation in this quotation process is entirely at the risk and cost of the bidder. PHTPB reserves the right to accept or reject any or all the quotations without assigning any reason.

3. Only courts situated in Chandigarh shall be competent in all matters relating to this Contract.
4. The quantities taken are tentative and can be increased/decreased as per actual requirement at site condition. No claim on account of variation in actual quantities shall be entertained.
5. The work shall be carried out as per Punjab, PWD specifications latest editions.
6. The rates quoted are inclusive of all taxes including GST.
7. The bill of quantities for the work is enclosed.
8. The Bidder shall quote its price as at par or percent above or percent below estimated total cost in the bill of quantities as specified there in.


Chief General Manager



Repair Work P.T.D.C Record Room

Bill of Quantities/Price Schedule						
Name of Bidder						
Note: Being a percentage tender, the bidder shall quote its price as at par or percent above or percent below the estimated total cost in the bill of Quantities as specified below:						
Sr. No.	CSR No.	Description	Unit	Qty.	Rate	Amount
1.	CSR 8.6 (d)	Dismantling concrete - Cement concrete plain 1:2:4 mix	Cum	0.95	1365	1296.75
2.	CSR 8.31 (c)	Scraping- Cement plaster	Sqm	40	36	1440.00
3.	CSR 13.55	Cement concrete 1:2:4 gola 10cm x 10cm concave quadrant along junction of roofs with parapet wall finished smooth, where specially specified.	Mtr	85	65	5525.00
4.	CSR 13.88	Water proofing treatment of RCC structures (after making the surface clean, dry & free from all internal voids or honey combs), with Zycosil /equivalent water proofing Solution (1 litre of Zycosil / equivalent & 20 litres of potable water stirred first & 2 litres of Zycoprime / equivalent added and stirred (total 23 litres)) using two coats till it meets the saturation level and testing as per RILEM or by water drops test in which water drops do not absorb but drops remain or rolls.	Sqm	52	236	12272.00
5.	CSR 15.8	12.5 mm thick cement plaster 1:3	Sqm	40	199	7960.00
Total						28494/-

Eidul

Ramesh